

## MODULAR POLYPROPYLENE VAULTS




### GET YOUR FIBER DEPLOYMENT BACK ON SCHEDULE.

- 18 to 22 weeks lead-time.
- Various sizes, tier ratings, and lid options.
- Modular vaults customizable to almost any traditional size and more.
- More efficient shipping, storage, and transportation to the deployment site.
- Contact us for details.



EASY BUILD SETUP



### COMMON VAULT SIZES

- 90 cm x 58 cm x 60 cm (35.4" x 22.8" x 23.6") Polypropylene Handhole B125 Composite Lid
- 113 cm x 90 cm x 80 cm (44.5" x 35.4" x 31.5") Polypropylene Handhole A15 Composite Lid
- 126 cm x 80 cm x 100 cm (49.6" x 31.5" x 39.4") Polypropylene Handhole D400 Cast Iron Steel Lid

\* Since these manholes are modular, the depth can easily be increased by adding 20 cm (7.9") modules.



HOW TO VIDEO